

SL No.	Particulars	Ammount in RS	CGST in RS.	SGST in RS.	Total Ammount RS
1	2MMD				
	a) 85 KW* 01 No.s Tariff LT3(138890*01=1,38,890/-)	1,38,890/-	0.0/-	0.0/-	1,38,890/-
2	5% Supervision Charges on (Total Estimate Cost Rs. 5,85,713/-)	29,286/-	2,636/-	2,636/-	34,557/-
3	Transformer Testing fees	1,000/-	0.0/-	0.0/-	1,000/-
4	LTMC Testing fees	4,080/-	0.0/-	0.0/-	4,080/-
Total Amount					1,78,527/-

6. As per **BESCOM** Circular No: BESCOM/ GM (QS&s) / DGM-3 /AGM- I /BC-11 / 2024 -25 /Cys-141, dt:05.12.2024.**Dry type transformers required to create infrastructure shall be purchased from BESCOM approved Vendors only.**
7. If **Dry type LBS/500KVA/CSS/transformer** has been installed under self execution, an under taking shall be furnished that the same shall be **maintained for life time by the applicant.**
8. As per **BESCOM**order No: **BESCOM/CGM(OP)/DGM (OP--1)/FY 2021-2022/CYS-19 Dt:17.05.2021.** The sub divisional officers ensure the **transformer quality** and rating at the authorized test bench/ Divisional stores **duly collecting transformer test certificate** issued by the concerned MT division before servicing of installation.
9. As per **BESCOM** Circular No: BESCOM/ GM (QS&s) / DGM-3 /AGM- I /BC-11 / 2024 -25 /Cys-15, dt:19.04.2024. **All dry type transformers procured under Self-execution shall be got tested at the nearest test bench center**and duly collecting transformer test certificate issued by the concerned MT division.
10. As per **BESCOM** Circular vide ref:-BESCOM/CGM(OP)/DGM(OP3)/2024-25/Cys-95 Dates:-15.02.2025& CYS-102 dated 25-03-2025, **The power supply shall be arranged to the above said installations through "Smart Energy Meter inline with its capacity and quantum of load requirement in BESCOM jurisdiction".**
11. **Guaranatee** shall be furnished for a period of not less than one year for the materials used in the works as well as for the quality of the work carried out from date taking over of the lines and equipments by **BESCOM.**
12. Provide **01 Nos of ETV Meter** with suitable CTs.
13. ಮುಖ್ಯ ಪ್ಯಾನೆಲ್ ಮತ್ತು ವಿತರಣಾ ಪ್ಯಾನೆಲ್‌ಗಳ ನಕ್ಷೆ ಮತ್ತು ವಿನ್ಯಾಸಗಳನ್ನು ಸಂಬಂಧಪಟ್ಟ ನಿಗಮದ ವಿಭಾಗದಿಂದ ಅನುಮೋದನೆ ಪಡೆಯತಕ್ಕದ್ದು ಮತ್ತು ಮಾಸ್ಟರ್ ಮಾಪಕವನ್ನು ಅಳವಡಿಸುವುದು.
14. ನಿಗಮದಿಂದ ಅನುಮೋದಿಸಲ್ಪಟ್ಟ **Vendors** ಗಳಿಂದ 5ಸ್ವಾರ್ ಹೊಂದಿರುವ ಸೂಕ್ತ ಸಾಮರ್ಥ್ಯದ ಪರಿವರ್ತಕವನ್ನು ಸ್ವಯಂ-ಕಾಮಗಾರಿ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಅನುಮೋದಿಸಿದ ಅಂದಾಜುಪಟ್ಟಿಯ ಪ್ರಕಾರ ಅಳವಡಿಸುವುದು.
15. Before commencement of work, **all material shall be inspected from the BESCOM authorities.**