



Bengaluru Electricity Supply Company Limited
(Wholly Owned Government of Karnataka Undertaking)
BESCOM GSTN No: 29AACCB1412G125

AEE/JIGANI (AET)

Office of the
Assistant Executive Engineer Ele.,
C,O&M, JIGANI Sub Division
BESCOM, JIGANI

To
SENIOR MANAGER
SY NO.254/1 PROP NO.522/43 TO 48 MADAPATTANA VILLAGE

Sir/Madam

Sub : Arranging power supply to an extent of 49.00 KW in favor of SENIOR MANAGER SY NO.254/1 PROP NO.522/43 TO 48 MADAPATTANA VILLAGE in JIGANI OMU, JIGANI

Ref: 1) Your application registration 1324105250007 dated 05-MAY-2025

2) AEE/JIGANI /AE(T) a/ 04-JUL-2025

With reference to your application dated 05-MAY-2025 . Requesting for arranging power supply to an extent of 49.00 KW power installations in favor of SENIOR MANAGER SY NO.254/1 PROP NO.522/43 TO 48 MADAPATTANA VILLAGE in JIGANI OMU, JIGANI Sub division in hereby sanctioned subject to the following Conditions.

a. You are requested to pay the following charges by DD/cash (above 10000/- only DD will be Accepted) payable at the Office of C, O&M JIGANI sub-division and furnish the payment certificate for taking further action in this matter.

Application No	Sub Application No	Tariff	Requested Load	Account Head	Amount(Rs.)
1324105250007	13241052500070001	LT6(C)- ELECTRIC VEHICLE CHARGING - LT6C	49.00 KW	61.9047-(WITH TAX) 5% Supervisory Charge(61.904)+CGST(46.9977)9%+SGST(46.9987)9%= (19507 + (19507*0.09) + (19507*0.09))	19507
1324105250007	13241052500070001	LT6(C)- ELECTRIC VEHICLE CHARGING - LT6C	49.00 KW	61.9067-61.9067-TRANSFORMER TESTING FEE+CGST(46.9977)9%+SGST(46.9987)9%=(1000 + (1000*0.09) + (1000*0.09))	1000
1324105250007	13241052500070001	LT6(C)- ELECTRIC VEHICLE CHARGING - LT6C	49.00 KW	48.1017-48.1017 - ISD+CGST(46.9977)9%+SGST(46.9987)9%=(45080 + (45080*0.09) + (45080*0.09))	45080
Total Amount in Rupees					65587

- b. The power supply will be arranged at 400V .
- c. The Tariff applicable to your installation will be LT6(C), or the Tariff in force From time to time.
- d. You have to enter into an agreement with the BESCOM in the prescribed form.
- e. Submit the Contractor's Completion-Cum-Test Report along with diagram in Duplicate.
- f. You shall install LT metering panel approved by the BESCOM with suitable Capacity MCCB and/or ELCB.
- g. Energy meter should be placed outside the premises at the height of 5ft from the ground level.
- h. Amount through DD should be paid in the name AEE BESCOM JIGANI .
- i. Intimation is valid up to 30 days from the date of issue.

In case the above requirements are not fulfilled within one month from the date of this communication, the sanction of power and registration will stand CANCELLED. The registration fee paid will be FOREFEITED. You are requested to contact the Asst. Ex. Engineer Ele., JIGANI Sub division, BESCOM for information and further needful.



ಬೆಂಗಳೂರು ವಿದ್ಯುತ್ ಸರಬರಾಜು ಕಂಪನಿ ನಿಯಮಿತ

(ಸಂಪೂರ್ಣ ಕರ್ನಾಟಕ ರಾಜ್ಯ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ)

ಸಂಖ್ಯೆ: ಅಇಂ(ವಿ)/ರಾವ್ಯ/ಕಾಇಂ(ಕ)/ಸಕಾಇ/2025-26/

ಲಗತ್ತು:

1164 - 66

Email: sermgc.work@gmail.com

Phone No. 080-28488780

BESCOM GST NO: 29AACCB1412G1Z5

ರವರ ಕಛೇರಿ,

ಅಧೀಕ್ಷಕ ಇಂಜಿನಿಯರ್(ವಿ),

ವಾಣಿಜ್ಯ, ಕಾರ್ಯ & ಪಾಲನಾ ರಾಮನಗರ ವೃತ್ತ,

ಬೆಂಗಳೂರು, ಟಿಪ್ಪಣಿ ಕಟ್ಟಡ, ಕೆಂಗೇರಿ,

ಬೆಂಗಳೂರು-560060.

To

M/s. Hindustan Petroleum Corporation Limited,

Sy No. 254/1,

Prop No. 522/43 to 48,

Madapattana Village,

Jigani Hobli,

Anekal Taluk,

22 MAY 2025

ಅಧಿಕ ವಿದ್ಯುತ್ ಭಾರ

ವ್ಯಾಪ್ತರೆ,

ವಿಷಯ: ನಿಮ್ಮ ಹಾಲಿ ಬಹುಮಹಡಿ ಕಟ್ಟಡಕ್ಕೆ ಅಧಿಕ 49 ಕಿ.ವ್ಯಾ (ಹಾಲಿ 19 ಕಿ.ವ್ಯಾ + ಅಧಿಕ 49 ಕಿ.ವ್ಯಾ; ಒಟ್ಟು 68 ಕಿ.ವ್ಯಾ) ಅಧಿಕ ವಿದ್ಯುತ್ ಭಾರ (ಇ.ವಿ ಚಾರ್ಜಿಂಗ್) ಉದ್ದೇಶಕ್ಕೆ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಕಲ್ಪಿಸುವ ಬಗ್ಗೆ.

ಉಲ್ಲೇಖ: ಕಾನಿಇಂ(ವಿ)/ಚಂದಾ /ಸಕಾನಿಇಂ(ಕ)/ಸಇಂ(ತಾಂ)/2025-26/1473-74 ದಿ: 19.05.2025 ಚಂದಾಮರ ವಿಭಾಗ.

9036130736

Application ID: 1324105250007

ನಿಮ್ಮ ಮನವಿಯಲ್ಲಿ ನೀವು ಕೋರಿರುವಂತೆ ಅಧಿಕ 49 ಕಿ.ವ್ಯಾ (ಹಾಲಿ 19ಕಿ.ವ್ಯಾ + ಅಧಿಕ 49 ಕಿ.ವ್ಯಾ; ಒಟ್ಟು 68 ಕಿ.ವ್ಯಾ) ವಿದ್ಯುತ್ ಭಾರವನ್ನು ಕೆ.ಇ.ಆರ್.ಸಿ ನಿಯಮ 3.1.5ರ ಪ್ರಕಾರ ಈ ಕೆಳಗೆ ಸೂಚಿಸಿರುವ ಷರತ್ತುಗಳ ಮೇರೆಗೆ ಮಂಜೂರು ಮಾಡಲಾಗಿದೆ ಹಾಗೂ ಮಂಜೂರಾತಿಯು ಈ ದಿನಾಂಕದಿಂದ 90 ದಿವಸಗಳವರೆಗೆ ಚಾಲ್ತಿಯಲ್ಲಿರುತ್ತದೆ. (ಹಾಲಿ 19 ಕಿ.ವ್ಯಾ + ಅಧಿಕ 49ಕಿ.ವ್ಯಾ; ಒಟ್ಟು 68ಕಿ.ವ್ಯಾ).

1. ತಾವು ಹಾಲಿ ಕಟ್ಟಿರುವ ಕಟ್ಟಡದ ವಿಸ್ತೀರ್ಣ 1643 ಚ.ಮೀ, Ground Floor ಇರುತ್ತದೆ. ಹೊಸದಾಗಿ ನೀವು ಕೋರಿರುವ ಅಧಿಕ ವಿದ್ಯುತ್ ಪ್ರಮಾಣ 49 ಕಿ.ವ್ಯಾ (ಇ.ವಿ ಚಾರ್ಜಿಂಗ್)
2. ಸದರಿ ಸ್ಥಾವರಕ್ಕೆ ಹಾಲಿ ಇರುವ F-5 SLV Feeder, 66/11KV Jigani old MUSS ಉಪಸ್ಥಾವರದಿಂದ ವಿದ್ಯುತ್ ಸರಬರಾಜು ಮಾಡಲಾಗುವುದು.
3. ಚಾಲ್ತಿಯಲ್ಲಿರುವ ಎಲ್.ಟಿ.-6C ಜಕಾತಿಯು ನಿಮ್ಮ ಸ್ಥಾವರಕ್ಕೆ ಅನ್ವಯಿಸಲಿರುತ್ತದೆ.
4. ಈ ಕೆಳಕಂಡ ಠೇವಣಿ/ಶುಲ್ಕಗಳನ್ನು ಸ.ಕಾ.ನಿ.ಇಂ(ವಿ), ಜಿಗಣಿ ಉಪ-ವಿಭಾಗದಲ್ಲಿ DD ಮೂಲಕ ಪಾವತಿಸುವುದು.

Page 1 of 4

Applicant Name: M/s. Hindustan Petroleum Corporation Limited,

Application ID: 1324105250007

Sl No	Particulars	Amount (in Rs.)	9 % CGST (in Rs.)	9% SGST (in Rs.)	Amount Rs.
1	2MMD:				
	a) 49KW * 01 Nos: Tariff LT-6c (45,080) on Existing RR No. MPP-30(EX load 19KW +Add Load 49KW = Total Load 68KW)	45,080/-	0	0	45,080/-
2	5% Supervision Charges on (Total Estimate Cost Rs. 3,97,643/-)	19,507/-	1756/-	1756/-	23,018/-
3	Transformer Testing fee	1,000/-	0	0	1,000/-
Total Amount					69,098/-
(Rupees Sixty nine thousand and Ninety eight only)					

- As per **BESCOM** Circular No: BESCOM/ GM (QS&s) / DGM-3 /AGM- 1 /BC-11 / 2024 -25 /Cys-141. dt:05.12. 2024.Dry type transformers required to create infrastructure shall be purchased from **BESCOM** approved Vendors only.
- If Dry type LBS/500KVA/CSS/transformer has been installed under self-execution, an under taking shall be furnished that the same shall be maintained for life time by the applicant.
- As per **BESCOM** order No: BESCOM/CGM(OP)/DGM (OP-1)/FY 2021-2022/CYS-19 Dt:17.05.2021. The sub divisional officers ensure the transformer quality and rating at the authorized test bench/ Divisional stores duly collecting transformer test certificate issued by the concerned MT division before servicing of installation.
- As per **BESCOM** Circular No: BESCOM/ GM (QS&s) / DGM-3 /AGM- 1 /BC-11 / 2024 -25 /Cys-15. dt:19.04.2024. All dry type transformers procured under Self-execution shall be got tested at the nearest test bench center and duly collecting transformer test certificate issued by the concerned MT division.
- As per **BESCOM** Circular vide ref:-BESCOM/CGM(OP)/DGM(OP3)/2024-25/Cys-95 Dates:- 15.02.2025 & CYS-102 dated 25-03-2025. The power supply shall be arranged to the above said installations through "Smart Energy Meter in line with its capacity and quantum of load requirement in **BESCOM** jurisdiction".
- Guanatee shall be furnished for a period of not less than one year for the materials used in the works as well as for the quality of the work carried out from date taking over of the lines and equipments by **BESCOM**.
- Provide 01ETV Meter with suitable CTs.
- ಮುಖ್ಯ ಪ್ಯಾನೆಲ್ ಮತ್ತು ವಿತರಣಾ ಪ್ಯಾನೆಲ್‌ಗಳ ನಕ್ಷೆ ಮತ್ತು ವಿನ್ಯಾಸಗಳನ್ನು ಸಂಬಂಧಪಟ್ಟ ನಿಗಮದ ವಿಭಾಗದಿಂದ ಅನುಮೋದನೆ ಪಡೆಯತಕ್ಕದ್ದು ಮತ್ತು ಮಾಸ್ಟರ್ ಮಾಪಕವನ್ನು ಅಳವಡಿಸುವುದು.

Applicant Name: M/s. Hindustan Petroleum Corporation Limited,

Application ID: 1324105250007

13. ನಿಗಮದಿಂದ ಅನುಮೋದಿಸಲ್ಪಟ್ಟ Vendors ಗಳಿಂದ 5 ಸ್ಟಾರ್ ಹೊಂದಿರುವ ಸೂಕ್ತ ಸಾಮರ್ಥ್ಯದ ಪರಿವರ್ತಕವನ್ನು ಸ್ವಯಂ-ಕಾಮಗಾರಿ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಅನುಮೋದಿಸಿದ ಅಂದಾಜುಪಟ್ಟಿಯ ಪ್ರಕಾರ ಅಳವಡಿಸುವುದು.
14. Before commencement of work, all material shall be inspected from the BESCOM authorities.
15. ನಿಮ್ಮ ಕಟ್ಟಡಕ್ಕೆ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಅಳವಡಿಸುವ ಮುನ್ನ ನಿಯಮಾನುಸಾರ ಸೋಲಾರ್ ವಾಟರ್ ಹೀಟರ್ ಗಳನ್ನು ಕಡ್ಡಾಯವಾಗಿ ಅಳವಡಿಸುವುದು.
16. ವಿದ್ಯುತ್ ಸಂಪರ್ಕಕ್ಕಾಗಿ ನೀವು ಸಲ್ಲಿಸಿರುವ ಬಿ.ಬಿ.ಎಂ.ಪಿ./ಬಿ.ಎಂ.ಆರ್.ಡಿ.ಎ./ನಗರ ಪಾಲಿಕೆ/ಗ್ರಾಮ ಪಂಚಾಯಿತಿಯಿಂದ ಅನುಮೋದನೆಗೊಂಡ ನಕ್ಷೆ/ಮಾಲೀಕತ್ವದ ದಾಖಲೆಗಳು ಹಾಗೂ ಇತರೆ ದಾಖಲಾತಿಗಳು ಸಕಲ/ಸುಳ್ಳು ಎಂದು ಕಂಡು ಬಂದಲ್ಲಿ ಯಾವುದೇ ಮುನ್ಸೂಚನೆ ನೀಡದೆ ನಿಮ್ಮ ಕಟ್ಟಡಕ್ಕೆ ವರ್ಗದಿಸಿದ್ದ ವಿದ್ಯುತ್ ಸಂಪರ್ಕವನ್ನು ಕಡಿತಗೊಳಿಸಲಾಗುವುದು ಮತ್ತು ನೀವು ಬಿ.ಬಿ.ಕಂ.ಗೆ ಪಾವತಿಸಿರುವ ರೇವಣಿಗಳನ್ನು ಮುಟ್ಟುಗೋಲು ಹಾಕಿಕೊಳ್ಳಲಾಗುವುದು.
17. ನಿಮ್ಮ ಕಟ್ಟಡದ ಎತ್ತರ 15 ಮೀ ಮತ್ತು ಅದಕ್ಕಿಂತ ಜಾಸ್ತಿ ಇದ್ದರೆ ನಿಯಮಾನುಸಾರ ವಿದ್ಯುತ್ ಪರಿವೀಕ್ಷಕರ ಅನುಮತಿಯನ್ನು ಪಡೆಯಬೇಕು.
18. (a) An electrical room with RCC roof having clear floor area of 5 metres X 4 metres with a vertical clearance of 2.75 meters with locking facility, exhaust fans and adequate size of cable duct, shall be provided at the ground floor within the Applicant's premises nearer to the main entrance for installing floor mounted distribution transformer and associated switchgear or
(b) A clear space of 3 metres X 5 metres open to the sky shall be provided within the Applicant's premises preferably at the main entrance for installing structure mounted distribution transformer and switchgear.
19. ನಿಗಮದಿಂದ ಅನುಮೋದಿಸಲ್ಪಟ್ಟ ಸೂಕ್ತ ಸಾಮರ್ಥ್ಯದ ಸರ್ಕ್ಯೂಟ್ ಬ್ರೇಕರ್ ಮತ್ತು ಇ.ಎಲ್.ಸಿ.ಬಿ.ಯನ್ನು ಮಾಪಕ ಪೆಟ್ಟಿಗೆಯಿಂದ ಒಂದು ಮೀಟರ್ ಒಳಗೆ ಮತ್ತು ಭೂಮಿಯಿಂದ 0.6 - 1.6 ಮೀ ಎತ್ತರದ ಒಳಗೆ ನೆಲ ಮೇಲೆಗಿಯಲ್ಲಿ ಅಳವಡಿಸುವುದು.
20. ನಿಮ್ಮ ಆವರಣದಲ್ಲಿ ಹಾಲಿ ಇರುವ 1*25 ಕೆ.ವಿ. ಎ (Open Bushing type) ಪರಿವರ್ತಕದಿಂದ 1*100 ಕೆ.ವಿ. ಎ (Open Bushing type) ಪರಿವರ್ತಕಕ್ಕೆ ಮೇಲ್ದರ್ಜೆಗೇರಿ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಕಲ್ಪಿಸಲಾಗುವುದು.
21. ನಿಮ್ಮ ಆವರಣದಲ್ಲಿ ಹಾಲಿ ಸ್ಥಾಪಿಸಿರುವ 1*63 ಕೆ.ವಿ.ಎ ಪರಿವರ್ತಕದಿಂದ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಕಲ್ಪಿಸಲಾಗುವುದು.
22. ಈ ಪತ್ರದಲ್ಲಿ ನಮೂದಿಸಿರುವ ರೇವಣಿಗಳನ್ನು ಪಾವತಿಸಿದ ನಂತರ, ವೈರಿಂಗ್ ನಕ್ಷೆ, ಗುತ್ತಿಗೆದಾರರ ಸಮಾಪನಾ ವರದಿ ಮತ್ತು ಒಪ್ಪಂದ ಪ್ರತಿಗಳನ್ನು ಸಂಬಂಧಪಟ್ಟ ಉಪ-ವಿಭಾಗದಲ್ಲಿ ಸಲ್ಲಿಸುವುದು.
23. ಹೆಚ್ಚಿನ ಮಾಹಿತಿಗಾಗಿ ಚಂದಾಮೂರ ವಿಭಾಗದ ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್(ವಿ),ಜಿಗಣಿ ಉಪ-ವಿಭಾಗದ, ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್ (ವಿ) ಅವರನ್ನು ಸಂಪರ್ಕಿಸುವುದು.
24. ಸದರಿ ಸ್ಥಾವರಕ್ಕೆ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಕಲ್ಪಿಸುವ ಸಂದರ್ಭದಲ್ಲಿ KERC ರವರ clause-9 ರನ್ವಯ ಹಾಗೂ KERC upto date Amendment ಗಳನ್ವಯ ಕ್ರಮ ಕೈಗೊಳ್ಳುವುದು.
25. ಭವಿಷ್ಯದಲ್ಲಿ, ಯಾವುದೇ ವ್ಯತ್ಯಾಸದ ಮೊತ್ತವು ಪಾವತಿಸಬೇಕಾದಲ್ಲಿ ಕೊಡಲೇ ಅದನ್ನು ಬೆವಿಕಂ ಗೆ ಪಾವತಿಸಬೇಕು.
26. ಸದರಿ ಗ್ರಾಹಕರು ಅನುಮೋದಿತ ನಕ್ಷೆಯ ಜೊತೆಗೆ ಹೆಚ್ಚುವರಿಯಾಗಿ ಮಹಡಿಗಳನ್ನು ನಿರ್ಮಿಸಿದ್ದರೆ, ಸದರಿ ಸಂಬಂಧವಾಗಿ ಯಾವುದೇ ಹೆಚ್ಚುವರಿ ಮೊತ್ತ/ದಂಡಕ್ಕೆ ಗ್ರಾಹಕರೇ ಜವಾಬ್ದಾರರಾಗಿರುತ್ತಾರೆ.

Applicant Name: M/s. Hindustan Petroleum Corporation Limited,

Page 3 of 4

Application ID: 1324105250007

- 28 The released materials, if any as per 7th schedule credit estimate shall be handed over to the concerned divisional stores.
- 29 The materials used shall conform to the BESCOM Specifications. Joint inventory should be submitted after completion of work.
- 29 Before execution of work the above mentioned License Electrical contractor has to obtain consent letter from the AEE (Ele) of the concerned sub-division for execution of works taking up all the safety measures and the concerned section officer before issuing the Line Clear has to confirm the same with the AEE (Ele) of their respective sub-division & contractor.
- 30 Precommissioning report from cables from BESCOM authorities, shall be obtained for the newly laid cables under self execution works before connecting to the net work.
31. As per Govt Notification No. KERC/COS/DDD/1/2018-19/908, Bengaluru dated: 22.10.2019. In the conditions of supply of distribution licensees in the state of karnataka, 2006 after the existing clause 9.0, the following new clause shall be insertd, namely:-
9A.00-Applicable to Commercial/Residential Buildings (s)/Complex/MS Building (s) in
Metropolitan areas/Urban Development Authority Areas of all Cities/City Corporation areas in
the state of karnataka where:
 - a) The requested load is **250KW or More: or**
 - b) The built-up area of the building is **more than 5,000 Square meters**

The Owner/Promoter/Occupier of the above building shall also provide not less than two number of charging points capable of Charging Electric Vechicles, i.e four/three/two-wheeler with adequate space in such buildings.

ತಮ್ಮ ವಿಶ್ವಾಸಿ,

ಅಧೀಕ್ಷಕ ಇಂಜಿನಿಯರ್(ವಿ),
 ಬೆಂಗಳೂರು, ರಾಯನಗರ ವೃತ್ತ

Applicant Name: M/s. Hindustan Petroleum Corporation Limited,

Application ID: 1324105250007