BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED

CIN: U04010KA2002SGC030438

Website:www.Bescom.org

Email: sekolar@bescom.co.in, Seklrcircle.work@gmail.com

Phone No: 08152-220642

Phone No: 08152-220642 No: SEE/EE (O)/AEE (T)/AE-2/2025-26 6 HQQ -QH

Office of the,

Superintending Engineer (Ele), C, O & M Circle, BESCOM, Kolar.

Date:-

DEC 2025

To,

Sri. P Rajendra Prasad Reddy,

S/o Sri. Raghurami Reddy,

At #33, BP No. 367/33, Jodikrishnapura Village,

Bellur Gramapanchayath,

Kolar taluk.

Sir,

Sub: Arranging Power Sanction by to an extent of 85KWs as per MS reg-9- Under Self-Execution.

Ref: 1. EEE/AEE (O)/AE-1/KGF/2025-26/7206-08 Dated: 21.11.2025.

- $2.\ BESCOM/GM(QS\&S)/DGM-3/AGM-1/BC-11/2024-25/CYS-15\ Dated:\ 19.04.2024.$
- 3. Application No. 1221111250025.

With reference to the above, Application registered in Kolar Rural sub division, requesting for arranging power supply to an extent of 85KWs under LT-3(a) tariff in favor Sri. P Rajendra Prasad Reddy S/o Sri. Raghurami Reddy At #33, BP No. 367/33, Jodikrishnapura Village, Bellur Gramapanchayath in Narasapura Section of Rural Sub-division, Kolar Division as per MS reg-9.

Subject to the following Terms & Conditions:

- Power Sanction is valid for 90 days from this date.
- The Proposed load will be arranged under LT secondary 3 Phase 430 Volts to M S Building from erection and commissioning of 1 X100 KVA Dry Type Distribution Transformer as per M S reg-9 under Self-Execution.
- You have to provide LED bulbs in place of incandescent bulbs vide circular no: BESCOM/BC-9/1554/2010-11/4-5-2010 and also with solar heating system vide circular no: BESCOM/BC-9/414/2008-09/19-03-2010.
- Tariff applicable to your installations will be LT-3(a).
- Please enter in to an agreement with the BESCOM in the format prescribed and available in the application booklet.

You are requested to pay the following within 90days from this date, failing which this intimation will be deemed to be cancelled.

S.No.	Details	Amount to be paid	Remarks
1.	Supervision Charges 5% on Estimate cost of Rs. 10,06,303/- (Excluding DEI+Employees cost)	Rs. 50,315/-	Fifteen Thousand Three Hundred and Fifteen Only.
2.	ISD Charges	LT-3(a) 15KWs*01No.=Rs. 23,990/-* 01Nos 13KWs*01No.=Rs. 20,790/-* 01Nos 18KWs*01No.=Rs. 28,790/-* 01Nos 34KWs*01No.=Rs. 54,390/-* 01Nos 05KWs*01No.=Rs. 8,000/-* 01Nos	 Twenty Three Thousand Nine Hundred and Ninety Only. Twenty Thousand Seven Hundred and Ninety Only. Twenty Eight Thousand Seven Hundred and Ninety Only. Fifty Four Thousand Three Hundred and Ninety Only. Eight Thousand Only.
3.	Material Inspection charges	Rs. 20,000/-	Twenty Thousand Only.
4.	Transformer Testing Fees	Rs. 1,000/-	One Thousand Only.
5.	Supervision charges	Rs. 250/-	Two Hundred and Fifty only.

- As per BESCOM Circular: BESCOM/CGM(OP)/DGM(op-1)/AGM(Op-3)/AE-1/BC-05/2023-24/CYS-124 Dt 17.02.2024. to pay the Transformer Testing fee: Rs.1,000/ + GST 18%, Head of account:62-930 payable at: Division office, where the Transformers are tested.
- The above deposits are to be paid through DD in favour of Assistant Executive Engineer (Ele), C, O & M of Concerned sub division.
- Produce Payment Certificate duly certified by AAO/ Sr. Assistant with regards to deposit collected accounted
 and remitted to BESCOM accounts and by the Assistant Executive Engineer (Ele), C, O & M Rural sub
 division, for verification and further action.
- Vide circular no: BESCOM/CGM(OP)/DGM(OP-3)/2024-25/CYS-95 Dt: 15.02.2025, You have to purchase and provide necessary no. of Single/Three Phase Smart Meters from BESCOM approved outlet with sealing facility.
- It is instructed to follow the guidelines issued Vide Letter No. CGM(P)/DGM-3/BC-05/F-341/25-26/CYS-02 Dated: 04.04.2025.
- The Materials procured from approved vendor for this work shall be got inspected from the Assistant Executive Engineer(Ele), Q, S & S BESCOM Kolar, before they are used in the field
- · Copies of the invoices/ Bills for having purchased the materials, should furnish whenever necessary.
- Joint inventory Report duly signed by the BESCOM Officers and agencies as prescribed format
 vide Chief Controller of Accounts circular No:-AO/CYS-10/92-93/20-04- 1992 (page 246 of
 Compendium Vol-1) and Approval of the Electorate Inspectorate authorities shall be furnished
 (wherever applicable).
- The metering equipment is to be installed and should be conspicuously visible and at the main entrance to the premises preferably with independent entrance.
- Dry type transformer installed under SELF EXECUTION BASIS by the consumer shall be maintained for lifetime, an undertaking in Rs.200/- Stamp paper shall be submitted to the concerned Asst. Executive Engineer (Ele), O & M subdivision and follow the circular vide ref-2.
- The materials used shall conform to the relevant ISI specifications. The quality of the work such as depth of Planting of poles, erection of poles and transformer centres, stringing etc., shall be as per the standard drawings of the Licensee.
- The Transformer and switch gear used shall be of reputed make and approved by the Licensee from time to time. Manufacturers test report for the transformers and switchgears installed shall be obtained and approved by the authority competent to sanction the estimate.
- You have to submit the undertaking to the Assistant Executive Engineer (Ele), C, O & M Kolar Rural sub
 division, for the guarantee for a period of 5 year for the materials used as well quality of the work from the
 date of taking over of the lines and equipment s by the Licensee.
- You have to purchase and provide 1X100KVA Dry Type Distribution Transformer 11 KV/433 Volts, shall be conform to IS 1180-2014. Impedance %=4.5% the maximum total losses(W) (Energy Efficiency level-1) on 50% Load is 380 W and on 100% Load is 1050 W and all relevant line materials is to be purchase at BESCOM approved vendors only, and the proof of having purchasing materials used for executing the works from the reputed firm will be verified whenever necessary.
- You have to purchase and provide standard panel board with appropriated LT, CT's having a space for
 providing MASTER METER with Bus bar and sealing facility. The Drawing shall be got approved from the
 respective Executive Engineer (Ele) of concerned C, O&M division.
- If the building height is above 15 Mtrs, you have to obtain Approval for your installation by Electrical Inspectorate (Test and Commissioning Certificate) should be produced for servicing of your installation.
- Please furnish Licensed Electrical Contractor's completion report in Duplicate with test results.
- As per M.S reg-9, a clear space of 3 meters X 5 meters open to the sky shall be provided within the Applicants
 premises nearer to the main entrance for installing structure mounted distribution transformer and
 switchgear.
- Note: 1. In future any difference in deposits arises as per MS Regulation 9 you have to pay.
 - 2. BESCOM is not responsible in whatever manner regarding any of legal disputes that may arise and at later stage.
 - 3. For any other details you are requested to contact The Assistant Executive Engineer(Ele), BESCOM, C, O&M Kolar Rural sub division, or to The Executive Engineer(Ele), BESCOM, C, O &M division, Kolar.

Yours faithfully

Superintending Engineer (Ele), C, O & M Circle, BESCOM, Kolar

Copy to:

- 1. The Executive Engineer (Ele), BESCOM, C, O & M Division, Kolar for information.
- 2. The Assistant Executive Engineer (Ele), BESCOM, C, O & M Rural sub division, for information.