



Bangalore Electricity Supply Company Limited

(Wholly owned by Government of Karnataka Undertaking)

No: EEE/HKTD/AEB(O)/AE-1/2025-26/ 2144
12/6/25

Office of
Executive Engineer
C, O&M DIVISION HOSAKOTE

To

M/s Sobha Limited,
Mrs. V. Padmavathi,
Sy No. 45/4,
Huskuru Village,
Bidarahalli Hobli,
Bangalore East Taluk.

Sir/Madam,

Sub: - Arranging HT power supply to an extent of 75 KVA in HT-5 Tariff HT Temporary installation in favour of M/s Sobha Limited, represented by Mrs. V. Padmavathi at Sy No. 45/4, Huskuru Village, Bidarahalli Hobli, Bangalore East Taluk in Manduru O&M unit of Avalahalli Sub Division Under self execution.

- Ref: 1) Your Application Reg. No. 1125106250005 dated: 04.06.2025.
2) Letter No: AEE(Ele)/AVL/AE(T)/2025-26/1077 dt.11.06.2025.
3) ಮುಕ್ತಾಯ(ಕಾ)/ಉತ್ಪನ್ನ/ದಿ-5/ಕ-341/25-26/Cys -02 ದಿನಾಂಕ: 04.04.2025.

BESCOM is pleased to sanction for additional power supply to an extent of 75 KVA in HT-5 Tariff HT Temporary installation in favour of M/s Sobha Limited, represented by Mrs. V. Padmavathi at Sy No. 45/4, Huskuru Village, Bidarahalli Hobli, Bangalore East Taluk in Manduru O&M unit of Avalahalli Sub Division Under self execution subject to the following conditions:

1. Power supply will be arranged from F-6 BPL feeder of 66/11KV Hosakote SubStation.

2. You are requested to pay the following charges by DD/Cash (above 10000/- only DD will be accepted) payable at the office of the Asst. Executive Engineer (C,O&M), BESCOM Avalahalli Sub-Division within 90 Days from the date of this intimation and furnish the payment certificate for taking further action in this matter

Payment Towards	Amount(Rs.)
A.C.C	5,36,175
Fixed Charges	34,000
5% Supervision Charges	56,428
9% CGST on 5% Supervision Charges	5,079
9% SGST on 5% Supervision Charges	5,079
Total	6,36,761/-

Amt in Words: Six lakh thirty six thousand seven hundred sixty one only.

3. To Submit payment certificate along with Self execution agreement on Rs. 200/- stamp paper regarding obtaining of necessary line clearance from field staff for safe execution of works & to comply with all safety procedure duly using safety equipment's during the course of work after which a works certificate / permit will be issued to take up the works on Self execution basis.

4. The metering equipment to be installed should be conspicuously visible and at the main inference to the premises preferably with an independent entrance.

5. The power supply will be arranged at 11KV Voltage class.

6. You should own and install the necessary transformer at your end to receive and step it down to the required distribution voltage for your installation

It is proposed to provide 10/1A CT's with HT ETV Meter 1A class 0.2s accuracy with TOD feature 3CT's 3PT's metering cubicle.

P.T.O