



**BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED**  
(Wholly owned Government of Karnataka Undertaking)

No: SEE/RMGC/EE(O)/AEE(O)/25-26/

Encl: 5143 - 45

E-mail: sermgc.work@gmail.com

Ph No: 080-28488723/780

BESCOM GST NO: 29AACCB1412G1Z5

Office of the  
Superintending Engineer (EI)  
Ramanagara Circle  
BESCOM, Kengeri TTMC  
Building, Bangalore - 560 060.

To

Indian Oil Corporation Limited

(ABC Enterprises)

Sy. No. 176/3,

Bidaragere Village( Anekal- Attibele Road) ,

Kasaba Hobli, Anekal Taluk.

29 SEP 2025

" DCW POWER SANCTION "

ವಾನ್ಯರೆ,

ವಿಷಯ: ನಿಮ್ಮ ಕಟ್ಟಡಕ್ಕೆ 60 ಕಿ.ವ್ಯಾ (ಇ ವಿ ಚಾರ್ಜಿಂಗ್ ) ಉದ್ದೇಶಕ್ಕೆ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಕಲ್ಪಿಸುವ ಬಗ್ಗೆ.  
ಉಲ್ಲೇಖ: ಕಾನಿಇಂ(ವಿ)/ಚಂ/ಸಕಾನಿಇಂ(ಕ)/ಸಇಂ(ತಾಂ)/2025-26/6678-79 ದಿನಾಂಕ: 25.09.2025 ಚಂದಾಮರ  
ವಿಭಾಗ.

\*\*\*\*\*

Application ID:1321109250005

ನಿಮ್ಮ ಮನವಿಯಲ್ಲಿ ನೀವು ಕೋರಿರುವಂತೆ 60 ಕಿ.ವ್ಯಾ (ಇ ವಿ ಚಾರ್ಜಿಂಗ್ ) ವಿದ್ಯುತ್ ಭಾರವನ್ನು ಕೆ.ಇ.ಆರ್.ಸಿ ನಿಯಮ 3.15 / 3.1.3A ರ ಪ್ರಕಾರ ಈ ಕೆಳಗೆ ಸೂಚಿಸಿರುವ ಷರತ್ತುಗಳ ಮೇರೆಗೆ ಮಂಜೂರು ಮಾಡಲಾಗಿದೆ ಹಾಗೂ ಮಂಜೂರಾತಿಯು ಈ ದಿನಾಂಕದಿಂದ 90 ದಿವಸಗಳವರೆಗೆ ಚಾಲ್ತಿಯಲ್ಲಿರುತ್ತದೆ.

1. ಶಾಪ್ ಹಾಲಿ ಕಟ್ಟಿರುವ ಕಟ್ಟಡದ ವಿಸ್ತೀರ್ಣ 44.18 ಚ.ಮೀ. Ground Floor ಇರುತ್ತದೆ. ಹೊಸದಾಗಿ ನೀವು ಕೋರಿರುವ ಅಧಿಕ ವಿದ್ಯುತ್ ಪ್ರಮಾಣ 60 ಕಿ.ವ್ಯಾ (ಇ.ವಿ ಚಾರ್ಜಿಂಗ್)
2. ಸದರಿ ಸ್ಥಾವರಕ್ಕೆ ಹಾಲಿ ಇರುವ F-15 NJY ಫೀಡರ್, 66/11KV Anekal MUSS ಉಪಸ್ಥಾಪಿಸಿದ ವಿದ್ಯುತ್ ಸರಬರಾಜು ಮಾಡಲಾಗುವುದು.
3. ಚಾಲ್ತಿಯಲ್ಲಿರುವ ಎಲ್.ಟಿ.-6 (c) ಜಕಾತಿಯು ನಿಮ್ಮ ಸ್ಥಾವರಕ್ಕೆ ಅನ್ವಯಿಸಲ್ಪಡುತ್ತದೆ.
4. ತಮಗೆ ಸರಬರಾಜು ನೀಡಲು ತಗಲುವ DCW ಕಾಮಗಾರಿಯ ಅಂದಾಜು ಪಟ್ಟಿಯ ಮೊತ್ತ 8,62,585/- ಆಗಿರುತ್ತದೆ.
5. ಈ ಕೆಳಕಂಡ ಠೇವಣಿ/ಬುಲಗುಗಳನ್ನು ಸ.ಕಾ.ನಿ.ಇಂ(ವಿ), ಆನೇಕಲ್ ಉಪ-ವಿಭಾಗದಲ್ಲಿ DD ಮೂಲಕ ಪಾವತಿಸುವುದು.

Page 1 of 4

Applicant Name: Indian Oil Corporation Limited (ABC Enterprises)

Application ID: 1321109250005

Scanned with CamScanner

Scanned with CamScanner

| SL No                                                                            | Particulars                                                    | Amount in RS | 9% CGST In RS. | 9% SGST In RS. | Total Amount in RS |
|----------------------------------------------------------------------------------|----------------------------------------------------------------|--------------|----------------|----------------|--------------------|
| 1                                                                                | 2MMD                                                           |              |                |                |                    |
|                                                                                  | a) 60 KW*01No Tariff LT-6(c) (55200/-)                         | 55200/-      | 0              | 0              | 55,200/-           |
| 2                                                                                | DCW Charges                                                    | 862585       | 0              | 0              | 862585/-           |
| 3                                                                                | 10% ESCOM Establishment Cost on Total cost of the DCW estimate | 86259        | 7763           | 7763           | 101785/-           |
| 4                                                                                | Transformer Testing Fees                                       | 1,000/-      | 0              | 0              | 1,000/-            |
| 5                                                                                | LT Meter Cubicle Testing Fees                                  | 4,080/-      | 0              | 0              | 4,080/-            |
| Total Amount (Ten Lakhs Twenty four Thousand six hundred and Fifty Rupees Only). |                                                                |              |                |                | 10,24,650/-        |

- As per BESCOM order No: CGM(OP)/DGM(OP-1)/AGM(OP-3)/AE-1/BC-05/2020-21/Cys-164 Dated: 29.03.2021. The Sub divisional officers ensure the transformer quality and rating at the authorized test bench/Divisional stores before servicing of installation and Amendment No. BESCOM/CGM(OP)/DGM(OP-1)AGM-3(OP-1)/AE-1(OP-1)/FY 2021-2022/CYS-19 Dated: 17.05.2021 the applicant has to test the transformer at BESCOM Centre by paying Rs.1000/- along with GST as mentioned in circular at the concerned division office, where the transformer are tested.
- Pre commissioning report from cable (W&M) Division, BESCOM shall be obtained for the newly laid cables under self-execution works before connecting to the network.
- Provide 01 ETV Meter with Suitable CTs.
- ಮುಖ್ಯ ಪ್ಯಾನೆಲ್ ಮತ್ತು ವಿತರಣಾ ಪ್ಯಾನೆಲ್‌ಗಳ ಸ್ಥಳ ಮತ್ತು ವಿಸ್ತಾರಗಳನ್ನು ಸಂಬಂಧಪಟ್ಟ ನಿಗಮದ ವಿಭಾಗದಿಂದ ಅನುಮೋದನೆ ಪಡೆಯತಕ್ಕದ್ದು ಮತ್ತು ಮಾಸ್ಟರ್ ಮಾಪಕವನ್ನು ಅಳವಡಿಸುವುದು.
- As per BESCOM order No: BESCOM/CGM(OP)/DGM (OP-1)/FY 2021-2022/CYS-19 Dt:17.05.2021. The sub divisional officers ensure the transformer quality and rating at the authorized test bench/ Divisional stores duly collecting transformer test certificate issued by the concerned MT division before servicing of installation.
- As per BESCOM Circular vide ref: BESCOM/CGM(OP)/DGM(OP3)/2024-25/Cys-95 Dates: - 15.02.2025 & CYS-102 dated 25-03-2025, The power supply shall be arranged to the above said installations through "Smart Energy Meter in line with its capacity and quantum of load requirement in BESCOM jurisdiction".
- ನಿಗಮದಿಂದ ಅನುಮೋದಿಸಲ್ಪಟ್ಟ 5 ಸ್ಟಾರ್ ಹೊಂದಿರುವ ಸೂಕ್ತ ಸಾಮರ್ಥ್ಯದ ಪರಿವರ್ತಕವನ್ನು DCW ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಅನುಮೋದಿಸಿದ ಅಂದಾಜು ಪಟ್ಟಿಯ ಪ್ರಕಾರ ಅಳವಡಿಸುವುದು.
- ನಿಮ್ಮ ಕಟ್ಟಡಕ್ಕೆ ವಿದ್ಯುತ್ ಸಂಪರ್ಕವರ್ಪಡಿಸುವ ಮುನ್ನ ನಿಯಮಾನುಸಾರ ಕಟ್ಟಡದ ಸುರಕ್ಷತೆಯ ಬಗ್ಗೆ ಬಿ.ಬಿ.ಎಂ.ಪಿ ನೋಡಲ್ ಅಧಿಕಾರಿಯಿಂದ/ಸಂಬಂಧಪಟ್ಟ ಅಧಿಕಾರಿಯಿಂದ ಅನುಮತಿಯನ್ನು ಪಡೆಯುವುದು.

Applicant Name: Indian Oil Corporation Limited (ABC Enterprises)  
Application ID: 1321109250005



26. ಸದರಿ ಗ್ರಾಹಕರು ಅನುಮೋದಿತ ನಕ್ಷೆಯ ಜೊತೆಗೆ ಹೆಚ್ಚುವರಿಯಾಗಿ ಮಹಡಿಗಳನ್ನು ನಿರ್ಮಿಸಿದ್ದರೆ, ಸದರಿ ಸಂಬಂಧವಾಗಿ ಯಾವುದೇ ಹೆಚ್ಚುವರಿ ಮೊತ್ತ/ದಂಡಕ್ಕೆ ಗ್ರಾಹಕರೇ ಜವಾಬ್ದಾರಾಗಿರುತ್ತಾರೆ.

27. 'As per the Circular No. BESCOM/GM(M&C)/DGM(M&C)/AGM-M1/2022-23/CYS-02 dt: 01.04.2022 The metering arrangement is mandatory w.e.f 01.04.2022 towards the consumer requisite load between 50KW to 150KW with LT metering cubicle having the specification and design as per the prototype approval comprising the following:

01 No. of CT & PT operated 02s accuracy class meter with provision for check meter.

03 Nos. of LT CTs of 0.2s accuracy class with burden of 2.5VA and secondary current 1A.

03 Nos. of LT PTs of 0.2 accuracy class with burden of 5VA and ratio 440/ - 3 /110 - 3 volts.

01 No. of Modem.

02No. Test Terminal Block and a suitable bus bar.

Note:

1. Intimation shall be issued to consumers in the power sanction letter to purchase LT metering cubicle from BESCOM approved VENDORS only.

2. All installations serviced with sanctioned load of 50KW to 150KW from 01.09.2021 to till date shall be replaced with the newly mentioned LT metering system as stated vide OM. OM No. BESCOM/GM(M&C)/DGM(M&C)/AGM-M1/2021-22/CYS-19 dt: 01.09.2021.

**Note:** For any 765/400/220/66/11 KV lines passing adjacent/nearby/on the premises, mandatory clearance certificate should be obtained from the competent authority by the developer / concerned EE of BESCOM before servicing of the installation. In case of any deviation in this regard concerned officers will be held responsible.

ತಮ್ಮ ವಿಶ್ವಾಸಿ,

P. R. [Signature] 27/09

ಅಧೀಕ್ಷಕ ಇಂಜಿನಿಯರ್ (ವಿ),

ಬೆವಿಕೂ, ರಾಮನಗರ ವೃತ್ತ