



Bangalore Electricity Supply Company Limited

(Wholly owned by Government of Karnataka Undertaking)

No: EEE/CDP/AEE (O)/JE-(T2)/2025-26/

4373-74

Office of
Executive Engineer (Ele)
C, O&M Division, BESCOM
No. 204, Park Road., Phase-1,
Suryacity, Chandapura.

1 AUG 2025

To

Sri. M Babu,
S/o Muniswamappa,
68/2/1, Near DLF apartment,
Rajapura Village,
Anekal Taluk.

Sir/Madam,

Sub: Arranging power supply to an extent of Addl. 185 KVA to the existing CD of 65 KVA totaling to 250 KVA of RR No. JGNHT-873 of Sri. M Babu S/o Muniswamappa, at # 68/2/1, Near DLF apartment, Rajapura Village, Anekal Taluk.

Ref: 1) Your Application Reg. No. 61324106250048 / 23.07.2025

2) Letter No: AEE/VS/RE(T)2025-26/1716/25.07.2025

BESCOM is pleased to sanction for Arranging power supply to an extent of Addl. 185 KVA to the existing CD of 65 KVA totaling to 250 KVA of RR No. JGNHT-873 of Sri. M Babu S/o Muniswamappa, at # 68/2/1, Near DLF apartment, Rajapura Village, Anekal Taluk

Subject to below conditions:

- Power supply will be arranged from F-1 Navya Feeder of 66/11 KV Jigani Bommasandra Link Road MUSS
- You are requested to pay the following charges by DD/Cash (above 10000/- only DD will be accepted) payable at the office of the Asst. Executive Engineer (C,O&M), BESCOM Jigani Sub-Division within 90 Days from the date of this intimation and furnish the payment certificate for taking further action in this matter

Deposit Held Rs. 3,60,000/-	
Deposit Required for 250 KVA under HT-2(A) tariff is Rs. 5,02,500/-	
Deposit to be paid Rs. 1,42,500/-	Tariff – HT-2a
Payment Towards	Amount(Rs.)
ISD	Rs. 1,42,500/-
5% Supervisory Charge(61.904) (On total Estimate cost Excluding Electrical Inspectorate Charges Rs. 46,970/-)	Rs. 2349/-
9% CGST	Rs. 211/-
9% CGST	Rs. 211/-
Total	Rs. 145271/-

3. To Submit payment certificate along with Self execution agreement on Rs. 500/- stamp paper regarding obtaining of necessary line clearance from field staff for safe execution of works & to comply with all safety procedure duly using safety equipment's during the course of work after which a works certificate / permit will be issued to take up the works on Self execution basis.

4. The metering equipment to be installed should be conspicuously visible and at the main inference to the premises preferably with an independent entrance.

6. You should own and install the necessary transformer at your end to receive and step it down to the required distribution voltage for your installation

It is proposed to replace the existing 5/1 Amps 3CT by 15/1 amps 3CT.

7. a) You should execute an agreement in the prescribed form and shall be submitted to the Executive Engineer Ele. of concerned division along with payment certificate.

b) Produce necessary Licensee/permit /NOC objection Certificate, etc. issued by the competent authorities as required under statute.

- c) Submit the completion-cum-test report from Class-I Licensed Electrical Contractor along with lists in duplicate showing details of machinery, make, capacity and the layout plan of your premises within which you intend to use the power. The capacity of any individual machinery equipment installed /connected shall not be more than the contract demand.
- d) You should produce the approval of competent authority of Electrical inspectorate to charge the equipment installed by you.
8. After payment of requisite supervisor charges and deposits and fulfillment of stipulated conditions administrative approval / certificate will be issued from this office.
9. You should comply with the following requirements within a period of 90 days from the date of this letter failing which, the sanction will stand cancelled.
- a) Execute an agreement in prescribed form on Rs.500/- stamp paper.
- b) Furnish the contractor's completion-cum test report along with a list in duplicate showing details of machinery, make, capacity and the layout plan, of your premises within which your intend to use the power. The capacity of any individual machinery / equipment installed / connected shall not be more than the contract demand.
10. You are liable to pay the tariff minimum charges from the date of commencement of supply i.e., actual date of availment of the power supply or expiry of 90 days of notice issued by BESCOM whichever is earlier as indicated in the agreement even if you fail to avail power supply.
11. The tariff applicable to your installation will be as per the prevailing power tariff i.e., HT-2a.
12. 11 KV System shall be as per BESCOM standard practices, the material used shall confirm ISI/BESCOM/KPTCL specification and got inspected before commencing of work by the under signed.
13. All the major materials like transformer, ACSR conductor, metering cubicle, HT UG cable, LT UG cable, 11 KV pin Insulator and 11 KV single/double break GOS shall be procured only from the BESCOM approved vendors. You have to use only 11 KVA polymeric type of insulator as per the directions of corporate office vide ltr. No. BESCOM/BC-9/CGM(CA)/DGM(CA-3)/F-752/13-14/Cys-113 dated 29.08.13.
14. You shall submit the copies of invoice/bills respect of materials purchased by you for proof of having purchased materials from approved vendors/dealers.
15. Guarantee shall be furnished for a period of not less than one year for the materials used in the works as well as quality of works carried out from the date taking over the lines and equipments by BESCOM.
16. You have to install approved shunt capacitors of appropriate capacity, so as to maintain the power factor at not less than 0.90.
17. If you are not desirous of availing the power supply, the amount paid by you towards initial security deposits, Meter security will be refunded on application, after deducting of 05% of the total amount.
18. The approval for your installation by electrical inspectorate (Test and Commissioning Certificate) should be produced for servicing of your installation.
19. You have to produce necessary license/permit/NOC from KSPCB before placing Work Order.
20. You have to produce necessary NOC from respective PGCIL/KPTCL if any EHT lines pass in premises before availing power supply to the layout /building.
21. For all EHT/HT/LT lines passing through the layout/building safety clearance to be maintained. (Statutory) are shifting of existing lines to be done at your cost.
22. BESCOM is not responsible in whatsoever manner regarding any of legal dispute that may arise at later stage.
23. The entire distribution system along with connected equipment's will be taken over by KPTCL/BESCOM after completion of work.
24. Intimation issued as per manual estimate.
25. Applicant has to follow the rules & Regulations as per the circular No: CGM(OP)/ DGM-3/BC-05/F-341/25-26 CYS-02 Dated : 04-04-2025 for availing power supply.

You are requested to contact Assistant Executive Engineer(Ele), Jigani Sub-Division, BESCOM or this office for any clarification.

Yours Sincerely,

Executive Engineer (Ele)
C, O&M Division, BESCOM
Chandapura