



# ಬೆಂಗಳೂರು ವಿದ್ಯುತ್ ಸರಬರಾಜು ಕಂಪನಿ ನಿಯಮಿತ

(ಸಂಪೂರ್ಣ ಕರ್ನಾಟಕ ರಾಜ್ಯ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ)

ಸಂಖ್ಯೆ: ಅಇಂ(ವಿ)/ರಾವ್ರ/ಕಾಇಂ(ಕ)/ಸಕಾಇ/2025-26/  
ಲಗತ್ತು:

Email: sermgc.work@gmail.com

Phone No. 080-28488780

BESCOM GST NO: 29AACCB1412G1Z5

ಅಧೀಕ್ಷಕ ಇಂಜಿನಿಯರ್(ವಿ)ರವರ ಕಛೇರಿ,  
ವಾ, ಕಾ & ಪಾ, ಬೆವಿಕಂ, ರಾಮನಗರ ವೃತ್ತ,  
ನಂ.285, ಎಲ್.ಜಿ. ಆರ್ಕೆಡ್,  
ಜ್ಞಾನಭಾರತಿ ಲೇಔಟ್, 2ನೇ ಹಂತ,  
ವಳಗೆರೆಹಳ್ಳಿ, 100 ಅಡಿ ಡಬಲ್ ರೋಡ್,  
ಶಿರ್ಕೆ ಅಪಾರ್ಟ್‌ಮೆಂಟ್ ಹತ್ತಿರ,  
ಕೆಂಗೇರಿ ಉಪನಗರ, ಬೆಂಗಳೂರು-560060.

To

Sri.Anil Kumar Dungarwala,

Sy No. 21/4,

Begihalli Village,

Anekal Taluk,

Jigani Sub-Division.

ವಾಸಸ್ಥಾನ,

ಅಧಿಕ ವಿದ್ಯುತ್ ಭಾರ

ವಿಷಯ: ನಿಮ್ಮ ಹಾಲಿ ಬಹುಮಹಡಿ ಕಟ್ಟಡಕ್ಕೆ ಅಧಿಕ 19 ಕಿ.ವ್ಯಾ (ಹಾಲಿ 30 ಕಿ.ವ್ಯಾ+ ಅಧಿಕ 19 ಕಿ.ವ್ಯಾ ಒಟ್ಟು 49 ಕಿ.ವ್ಯಾ) ಅಧಿಕ ವಿದ್ಯುತ್ ಭಾರ (ವಾಣಿಜ್ಯ) ಉದ್ದೇಶಕ್ಕೆ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಕಲ್ಪಿಸುವ ಬಗ್ಗೆ.

ಉಲ್ಲೇಖ: ಕಾನಿಇಂ(ವಿ)/ಚಂದಾ /ಸಕಾನಿಇಂ(ಕ)/ಸಇಂ(ತಾಂ)/2025-26/8098-99 ದಿ: 06.11.2025 ಚಂದಾಮರ ವಿಭಾಗ.

\*\*\*\*\*

**Application ID: 61324107250060**

ನಿಮ್ಮ ಮನವಿಯಲ್ಲಿ ನೀವು ಕೋರಿರುವಂತೆ ಅಧಿಕ 19 ಕಿ.ವ್ಯಾ (ಹಾಲಿ 30 ಕಿ.ವ್ಯಾ + ಅಧಿಕ 19 ಕಿ.ವ್ಯಾ ಒಟ್ಟು 49 ಕಿ.ವ್ಯಾ) ವಿದ್ಯುತ್ ಭಾರವನ್ನು ಕೆ.ಇ.ಆರ್.ಸಿ ನಿಯಮ 3.1.5ರ ಪ್ರಕಾರ ಈ ಕೆಳಗೆ ನೂಚಿಸಿರುವ ಷರತ್ತುಗಳ ಮೇರೆಗೆ ಮಂಜೂರು ಮಾಡಲಾಗಿದೆ ಹಾಗೂ ಮಂಜೂರಾತಿಯು ಈ ದಿನಾಂಕದಿಂದ 90 ದಿವಸಗಳವರೆಗೆ ಚಾಲ್ತಿಯಲ್ಲಿರುತ್ತದೆ. (ಹಾಲಿ 30 ಕಿ.ವ್ಯಾ + ಅಧಿಕ 19ಕಿ.ವ್ಯಾ ಒಟ್ಟು 49ಕಿ.ವ್ಯಾ).

1. ತಾವು ಹಾಲಿ ಕಟ್ಟಿರುವ ಕಟ್ಟಡದ ವಿಸ್ತೀರ್ಣ 371.6 ಚ.ಮೀ, **Ground Floor** ಇರುತ್ತದೆ. ಹೊಸದಾಗಿ ನೀವು ಕೋರಿರುವ ಅಧಿಕ ವಿದ್ಯುತ್ ಪ್ರಮಾಣ 19 ಕಿ.ವ್ಯಾ (ವಾಣಿಜ್ಯ)
2. ಸದರಿ ಸ್ಥಾವರಕ್ಕೆ ಹಾಲಿ ಇರುವ **F-15 Shivanahalli Feeder, 66/11KV Gollhalli MUSS** ಉಪಸ್ಥಾವರದಿಂದ ವಿದ್ಯುತ್ ಸರಬರಾಜು ಮಾಡಲಾಗುವುದು.
3. ಚಾಲ್ತಿಯಲ್ಲಿರುವ ಎಲ್.ಟಿ.-3 ಜಕಾತಿಯು ನಿಮ್ಮ ಸ್ಥಾವರಕ್ಕೆ ಅನ್ವಯಿಸಲ್ಪಡುತ್ತದೆ.
4. ತಮಗೆ ಸರಬರಾಜು ನೀಡಲು ತಗಲುವ ಸ್ವಯಂ ಕಾಮಗಾರಿ ಅಂದಾಜು ಪಟ್ಟಿಯ ವೆಚ್ಚ ರೂ.8,785/-ಆಗಿರುತ್ತದೆ
5. ಈ ಕೆಳಕಂಡ ಠೇವಣಿ/ಶುಲ್ಕಗಳನ್ನು ಸ.ಕಾ.ನಿ.ಇಂ(ವಿ), ಜಿಗಣಿ ಉಪ-ವಿಭಾಗದಲ್ಲಿ DD ಮೂಲಕ ಪಾವತಿಸುವುದು.

Page 1 of 4

**Applicant Name: Sri. Anil Kumar Dungarwala**

**Application ID: 61324107250060**

Sl No	Particulars	Amount (in Rs.)	9 % CGST (in Rs.)	9% SGST (in Rs.)	Total Amount in Rs.
1	2MMD:				
	a) 19KW * 01 Nos: Tariff LT-3 (31,160) on Existing RR No. BGHP-56(EX load 30KW +Add Load 19KW = Total Load 49KW)	31,160/-	0	0	31,160/-
2	5% Supervision Charges on (Total Estimate Cost Rs. 8,785/-)	189/-	17/-	17/-	223/-
Total Amount					31,383/-
(Rupees Thirty one thousand Three hundred and eighty three only)					

5. As per **BESCOM** Circular No: BESCOM/ GM (QS&s) / DGM-3 /AGM- I /BC-11 / 2024 -25 /Cys-141, dt:05.12. 2024.Dry **type transformers required to create infrastructure shall be purchased from BESCOM approved Vendors** only.
6. If **Dry type LBS/500KVA/CSS/transformer** has been installed under self-execution, an undertaking shall be furnished that the same shall be **maintained for life time by the applicant**.
7. As per **BESCOM** order No: **BESCOM/CGM(OP)/DGM (OP--1)/FY 2021-2022/CYS-19 Dt:17.05.2021**. The sub divisional officers ensure the **transformer quality** and rating at the authorized test bench/ Divisional stores **duly collecting transformer test certificate** issued by the concerned MT division before servicing of installation.
8. As per **BESCOM** Circular No: BESCOM/ GM (QS&s) / DGM-3 /AGM- I /BC-11 / 2024 -25 /Cys-15, dt:19.04.2024. **All dry type transformers procured under Self-execution shall be got tested at the nearest test bench center** and duly collecting transformer test certificate issued by the concerned MT division.
9. As per **BESCOM** Circular vide ref:-BESCOM/CGM(OP)/DGM(OP3)/2024-25/Cys-95 Dates:- 15.02.2025 & CYS-102 dated 25-03-2025, **The power supply shall be arranged to the above said installations through "Smart Energy Meter in line with its capacity and quantum of load requirement in BESCOM jurisdiction"**.
10. **Guanatee** shall be furnished for a period of not less than one year for the materials used in the works as well as for the quality of the work carried out from date taking over of the lines and equipments by **BESCOM**.
11. Provide 01ETV Meter with suitable CTs.

Applicant Name: **Sri. Anil Kumar Dungarwala**  
Application ID: 61324107250060

12. ಮುಖ್ಯ ಪ್ಯಾನೆಲ್ ಮತ್ತು ವಿತರಣಾ ಪ್ಯಾನೆಲ್‌ಗಳ ಸಕ್ಷೆ ಮತ್ತು ವಿನ್ಯಾಸಗಳನ್ನು ಸಂಬಂಧಪಟ್ಟ ನಿಗಮದ ವಿಭಾಗದಿಂದ ಅನುಮೋದಿಸಿ ಅಡ್ಡಿಯಲ್ಲಿ ಮತ್ತು ಮಾಸ್ಟರ್ ಮಾಪಕವನ್ನು ಅಳವಡಿಸುವುದು.
13. ನಿಗಮದಿಂದ ಅನುಮೋದಿಸಲ್ಪಟ್ಟ **Vendors** ಗಳಿಂದ 5 ಸ್ಟಾರ್ ಹೊಂದಿರುವ ಸೂಕ್ತ ಸಾಮರ್ಥ್ಯದ ಪರಿವರ್ತಕವನ್ನು ಸ್ಥಾನ-ಕಾಮಗಾರಿ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಅನುಮೋದಿಸಿದ ಅಂದಾಜುಪಟ್ಟಿಯ ಪ್ರಕಾರ ಅಳವಡಿಸುವುದು.
14. Before commencement of work, **all material shall be inspected from the BESCOM authorities.**
15. ನಿಮ್ಮ ಕಟ್ಟಡಕ್ಕೆ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಅಳವಡಿಸುವ ಮುನ್ನ ನಿಯಮಾನುಸಾರ ಸೋಲಾರ್ ವಾಟರ್ ಹೀಟರ್ ಗಳನ್ನು ಕಡ್ಡಾಯವಾಗಿ ಅಳವಡಿಸುವುದು.
16. ವಿದ್ಯುತ್ ಸಂಪರ್ಕಕ್ಕಾಗಿ ನೀವು ಸಲ್ಲಿಸಿರುವ ಬಿ.ಬಿ.ಎಂ.ಪಿ./ಬಿ.ಎಂ.ಆರ್.ಡಿ.ಎ./ಸಗರ ಪಾಲಿಕೆ/ಗ್ರಾಮ ಪಂಚಾಯತಿಯಿಂದ ಅನುಮೋದಿಸಲಾಗದ ಸಕ್ಷೆ/ಮಾಲೀಕತ್ವದ ದಾಖಲೆಗಳು ಹಾಗೂ ಇತರೆ ದಾಖಲಾತಿಗಳು ಸಕಲ/ಸುಳ್ಳು ಎಂದು ಕಂಡು ಬಂದಲ್ಲಿ ಯಾವುದೇ ಮುಷ್ಕಾಟವೇ ಸಿಡದೆ ನಿಮ್ಮ ಕಟ್ಟಡಕ್ಕೆ ಏರ್ಪಡಿಸಿದ್ದ ವಿದ್ಯುತ್ ಸಂಪರ್ಕವನ್ನು ಕಡಿತಗೊಳಿಸಲಾಗುವುದು ಮತ್ತು ನೀವು ಬಿ.ವಿ.ಕಂ.ಗೆ ಪಾವತಿಸಿರುವ ಠೇವಣಿಗಳನ್ನು ಮುಟ್ಟುಗೋಲು ಹಾಕಿಕೊಳ್ಳಲಾಗುವುದು.
17. ನಿಮ್ಮ ಕಟ್ಟಡದ ಎತ್ತರ 15 ಮೀ ಮತ್ತು ಅದಕ್ಕಿಂತ ಜಾಸ್ತಿ ಇದ್ದರೆ ನಿಯಮಾನುಸಾರ ವಿದ್ಯುತ್ ಪರಿವೀಕ್ಷಕರ ಅನುಮತಿಯನ್ನು ಪಡೆಯಬೇಕು.
18. (a) An electrical room with RCC roof having clear floor area of **5 metres X 4 metres** with a vertical clearance of 2.75 meters with locking facility, exhaust fans and adequate size of cable duct, shall be provided at the ground floor within the Applicant's premises nearer to the main entrance for installing floor mounted distribution transformer and associated switchgear or  
(b) A clear space of **3 metres X 5 metres** open to the sky shall be provided within the Applicant's premises preferably at the main entrance for installing structure mounted distribution transformer and switchgear.
19. ನಿಗಮದಿಂದ ಅನುಮೋದಿಸಲ್ಪಟ್ಟ ಸೂಕ್ತ ಸಾಮರ್ಥ್ಯದ ಸರ್ಕ್ಯೂಟ್ ಬ್ರೇಕರ್ ಮತ್ತು ಇ.ಎಲ್.ಸಿ.ಬಿ.ಯನ್ನು ಮಾಪಕ ಪೆಟ್ಟಿಗೆಯಿಂದ ಒಂದು ಮೀಟರ್ ಒಳಗೆ ಮತ್ತು ಭೂಮಿಯಿಂದ 0.6 - 1.6 ಮೀ ಎತ್ತರದ ಒಳಗೆ ನೆಲ ಮೇಲೆ ಇರಿಸಿ ಅಳವಡಿಸುವುದು.
20. ನಿಮ್ಮ ಆವರಣದಲ್ಲಿ ಹಾಲಿ ಸ್ಥಾಪಿಸಿರುವ 1\*63 ಕೆ.ವಿ.ಎ(OIL TYPE DTC) ಪರಿವರ್ತಕದಿಂದ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಕಲ್ಪಿಸಲಾಗುವುದು.
21. ಈ ಪತ್ರದಲ್ಲಿ ನಮೂದಿಸಿರುವ ಠೇವಣಿಗಳನ್ನು ಪಾವತಿಸಿದ ನಂತರ, ವೈರಿಂಗ್ ಸಕ್ಷೆ, ಗುತ್ತಿಗೆದಾರರ ಸಮಾಪನಾ ವರದಿ ಮತ್ತು ಒಪ್ಪಂದ ಪತ್ರಗಳನ್ನು ಸಂಬಂಧಪಟ್ಟ ಉಪ-ವಿಭಾಗದಲ್ಲಿ ಸಲ್ಲಿಸುವುದು.
22. ಹೆಚ್ಚಿನ ಮಾಹಿತಿಗಾಗಿ ಚಂದಾಮರ ವಿಭಾಗದ ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್(ವಿ),ಜಿಗಣಿ ಉಪ-ವಿಭಾಗದ, ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್ (ವಿ) ಅವರನ್ನು ಸಂಪರ್ಕಿಸುವುದು.
23. ಸದರಿ ಸ್ಥಾವರಕ್ಕೆ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಕಲ್ಪಿಸುವ ಸಂದರ್ಭದಲ್ಲಿ **KERC ರವರ clause-9** ರನ್ವಯ ಹಾಗೂ **KERC upto date Amendment** ಗಳನ್ವಯ ಕ್ರಮ ಕೈಗೊಳ್ಳುವುದು.
24. ಭವಿಷ್ಯದಲ್ಲಿ, ಯಾವುದೇ ವ್ಯತ್ಯಾಸದ ಮೊತ್ತವು ಪಾವತಿಸಬೇಕಾದಲ್ಲಿ ಕೊಡಲೇ ಅದನ್ನು ಬಿ.ವಿ.ಕಂ ಗೆ ಪಾವತಿಸಬೇಕು.
25. ಸದರಿ ಗ್ರಾಹಕರು ಅನುಮೋದಿತ ಸಕ್ಷೆಯ ಜೊತೆಗೆ ಹೆಚ್ಚುವರಿಯಾಗಿ ಮಹಡಿಗಳನ್ನು ನಿರ್ಮಿಸಿದ್ದರೆ, ಸದರಿ ಸಂಬಂಧವಾಗಿ ಯಾವುದೇ ಹೆಚ್ಚುವರಿ ಮೊತ್ತ/ದಂಡಕ್ಕೆ ಗ್ರಾಹಕರೇ ಜವಾಬ್ದಾರಾಗಿರುತ್ತಾರೆ.



26. The released materials, if any as per **7th schedule credit estimate** shall be handed over to the concerned divisional stores.
27. The materials used shall conform to the **BESCOM Specifications**, joint inventory should be submitted after completion of work.
28. Before execution of work the above mentioned License Electrical contractor has to obtain consent letter from the AEE (Ele) of the concerned sub-division for execution of works taking up all the safety measures and the concerned section officer before issuing the **Line Clear** has to confirm the same with the AEE (Ele) of their respective sub-division & contractor.
29. **Precommissioning report from cables from BESCOM authorities**, shall be obtained for the newly laid cables under self execution works before connecting to the net work.
30. As per Govt Notification No. KERC/COS/DDD/1/2018-19/908, Bengaluru dated:-22.10.2019. In the conditions of supply of distribution licensees in the state of karnataka, 2006 after the existing clause 9.0, the following new clause shall be inserted, namely-  
**"9A.00-Applicable to Commercial/Residential Buildings (s)/Complex/MS Building (s) in Metropolis areas/Urban Development Authority Areas of all Cities/City Corporation areas in the state of karnataka where:**
  - a) The requested load is **250KW or More; or**
  - b) The built-up area of the building is **more than 5,000 Square meters**

The Owner/Promoter/Occupier of the above building shall also provide not less than two number of charging points capable of **Charging Electric Vehicles, i.e four/three/two-wheeler with adequate space in such buildings.**

ತಮ್ಮ ವಿಶ್ವಾಸಿ,

ಅಧೀಕ್ಷಕ ಇಂಜಿನಿಯರ್(ವಿ),  
ಬೆವಿಕಂ, ರಾಮನಗರ ವೃತ್ತ

**ಪ್ರತಿಗಳನ್ನು:**

1. ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್(ವಿ), ಬೆವಿಕಂ, ಸಿ.ಒ.ಎಂ ಚಂದಾಮರ ವಿಭಾಗ ಇವರ ಮಾಹಿತಿಗಾಗಿ ಮತ್ತು ಸೂಕ್ತ ಕ್ರಮಕ್ಕಾಗಿ ಕಳುಹಿಸಲಾಗಿದೆ.
2. ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್(ವಿ), ಬೆವಿಕಂ, ಸಿ.ಒ.ಎಂ ಜಿಗಣಿ ಉಪ-ವಿಭಾಗ ಇವರ ಮಾಹಿತಿಗಾಗಿ ಹಾಗೂ ತಾವು ಹಣ ಪಾವತಿಸಿದ ದೃಢೀಕರಣದ ಪತ್ರವನ್ನು ನೀಡುವಾಗ ಈ ಕಛೇರಿಗೆ ಸಲ್ಲಿಸುವುದು.
3. ಕಾನಿಇಂ(ಕ)/ಸಕಾನಿಇಂ(ಕ)/ಮು.ಖ್ಯ ಕಡತಕ್ಕೆ.

Applicant Name: **Sri. Anil Kumar Dungarwala**  
Application ID: 61324107250060



**Bengaluru Electricity Supply Company Limited**  
(Wholly Owned Government of Karnataka Undertaking)

BESCOM GSTIN No: 29AACCB1412G125

AEE/JIGANI (AET)

Office of the  
Assistant Executive Engineer Ele.,  
C,O&M, JIGANI Sub Division  
BESCOM, JIGANI

To  
ANIL KUMAR DUNGARWAL  
BEGIHALLY—0

Sir/Madam

Sub : Arranging power supply to an extent of **49.00 KW** in favor of ANIL KUMAR DUNGARWAL BEGIHALLY---0 in JIGANI OMU, JIGANI

Ref: 1) Your application registration **61324107250060** dated **30-JUL-2025**

2) AEE/JIGANI /AE(T) a/ **15-NOV-2025**

With reference to your application dated **30-JUL-2025** . Requesting for arranging power supply to an extent of **49.00 KW** power installations in favor of ANIL KUMAR DUNGARWAL BEGIHALLY---0 in JIGANI OMU, JIGANI Sub division in hereby sanctioned subject to the following Conditions.

a. You are requested to pay the following charges by DD/cash (above 10000/- only DD will be Accepted) payable at the Office of C, O&M JIGANI sub-division and furnish the payment certificate for taking further action in this matter.

Application No	Sub Application No	Tariff	Requested Load	Account Head	Amount(Rs.)
61324107250060	2079596	LT3A-Rural-COMMERCIAL POWER & LIGHTING - LT3-RLB	49.00 KW	61.9047-( WITH TAX ) 5% Supervisory Charge(61.904)+CGST(46.9977)9%+SGST(46.9987)9%=(189 + (189*0.09) + (189*0.09))	223
61324107250060	2079596	LT3A-Rural-COMMERCIAL POWER & LIGHTING - LT3-RLB	49.00 KW	48.1037-48.1037 - ASD	8290
Total Amount in Rupees					8513

b. The power supply will be arranged at 0V .

c. The Tariff applicable to your installation will be LT3A-Rural, or the Tariff in force From time to time.

d. You have to enter into an agreement with the BESCOM in the prescribed form.

e. Submit the Contractor's Completion-Cum-Test Report along with diagram in Duplicate.

f. You shall install LT metering panel approved by the BESCOM with suitable Capacity MCCB and/or ELCB.

g. Energy meter should be placed outside the premises at the height of 5ft from the ground level.

h. Amount through DD should be paid in the name AEE BESCOM JIGANI .

i. Intimation is valid up to 30 days from the date of issue.

In case the above requirements are not fulfilled within one month from the date of this communication, the sanction of power and registration will stand CANCELLED. The registration fee paid will be FOREFEITED. You are requested to contact the Asst. Ex. Engineer Ele., JIGANI Sub division, BESCOM for information and further needful.

Your's Faithfully,

Assistant Engineer (Technical),  
JIGANI, BESCOM

Your's Faithfully,

Assistant Executive Engineer Ele.,  
JIGANI, BESCOM