



BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED

(Wholly owned Government of Karnataka Undertaking)

No. SEE/BRC/EE(O)/AEE(O)/F-1(B)/2025-26/ 9046-48

Office of the
Superintending Engineer (Ele),
(C, O&M), Blore Rural Circle,
BESCOM, KSSCL, 5th Floor,
"Beeja Bhavan", Bellary Road,
Hebbal, Bangalore -560024.

Date: 06 MAR 2026

Encl:

Ph No. 080-28482437 / 9448279007
Email ID: sebrca@bescom.co.in

To,
M/s. Indian Oil Corporation Limited represented by it's
Retail Manager Mahesh.S, Sy No. 43/1, 43/2, 43/4, 43/5,
44/1, 44/2 & 44/3, Yedehalli Village, Sompura Hobli,
Nelamangala Taluk-562111.

Sir,

Sub:

Arranging power supply to an extent of 120 KW EV Charging Station under LT-6(c) in favour of M/s. Indian Oil Corporation Limited represented by it's Retail Manager Mahesh.S, Sy No. 43/1, 43/2, 43/4, 43/5, 44/1, 44/2 & 44/3, Yedehalli Village, Sompura Hobli, Nelamangala Taluk in Dabaspete Sectoin of Dabaspete Sub-division of Nelamangala Division, "Under DCW Basis". (Application ID: 1113101260182)

- Ref:
1. As per 7th Amendment & 11th Amendment of ROE.
 2. Corporate office circular No. BESCOM/CGM(O)/DGM(OP-3)/AGM-1/21-22/Cys-134 Dated: 09.11.2021.
 3. KERC/COS/DDD/1/2018-19/908, Bengaluru Dated: 22.10.2019,
 4. Meeting Proceeding Ltr No. BESCOM/CGM(OP)/DGM(EV)/BC-3/2023-24/716 Dated: 12.12.2023.
 5. BESCOM/BC-53/CGM(OP)/DGM(EV)/2023-24/362 Dated: 18.08.2023.
 6. BESCOM/CGM(OP)/DGM(OP3)/AGM(OP)/2024-25/CYS-70 Dated: 07.10.2024.
 7. EEE/NEL/AEE(O)/AET/2025-26/15488-89 Dated: 27.02.2026.
 8. T.O Note Approved Dated: 05.03.2026.

With reference to the above BESCOM is pleased to sanction power to execute the work of arranging power supply to an extent of 120 KW EV Charging Station under LT-6(c) in favour of M/s. Indian Oil Corporation Limited represented by it's Retail Manager Mahesh.S, Sy No. 43/1, 43/2, 43/4, 43/5, 44/1, 44/2 & 44/3, Yedehalli Village, Sompura Hobli, Nelamangala Taluk in Dabaspete Sectoin of Dabaspete Sub-division of Nelamangala Division, "Under DCW Basis". subject to the following conditions:

- 1) The 11 kV line of DF-14 Biogen feeder feeding from 66/11KV Dabaspete MUSS. The Station installed Capacity of 2x31.5 MVA & the Station peak load is 27.70 MW. The feeder peak load of 400 Amps. The HTVR works out 6.12%.
- 2) You have to pay the following amount at Dabaspete Sub-division, BESCOM within a period of 90 days from the date of this power sanction.
- 3) The Total Estimate Costing of Rs. 13,26,974/- "Under DCW basis". (Application ID: 1113101260182)

S/No	Deposit details	Amount in Rs
1	2MMD for 120 KW under LT-6(c)	Rs. 1,09,680/- x 01
2	DCW Cost	Rs. 13,26,974/-
3	5% Tender Premium on DCW Cost	Rs. 66,349/-
4	9% CGST	Rs. 5,971/-
5	9% SGST	Rs. 5,971/-
6	5% ESCOM Establishment Cost on Total DCW Cost	Rs. 66,349/-
7	9% CGST	Rs. 5,971/-
8	9% SGST	Rs. 5,971/-

- 4) The clause 8.14(ii) is applicable defined in COS of KERC.
As per reference-5, the Metering arrangements for consumer availing load between 50 KW to 150 KW at low tension shall be as follows:
 - a. 01 No of CT & PT operated 0.2S accuracy class meter with provision for check meter.
 - b. 03 Nos of LT CT's of 0.2s accuracy class with burden of 2.5 VA and secondary current 1A.
 - c. 03 Nos of LT PT's of 0.2 accuracy class with burden of 5 VA and ration 40/3/110/3 volts.
 - d. 01 No. of Modern
 - e. 02 No of test terminal Block and suitable bus bar.
- 5) You should abide by the conditions of supply of electricity of Distribution Licensees in State of Karnataka in force with subsequent amendments.
- 6) The materials used shall confirm to ISI /BESCOM/KPTCL specifications and the materials procured should be got inspected before commencing of work by TA & QC or BESCOM authorities.
- 7) You shall submit copies of the invoices / bills in respect of materials purchased by you for proof of having purchased the materials from the approved vendors /dealers.

the major materials like Distribution transformer & transformer mounting structures, ACSR conductor, HT UG cable, LT UG cable, 11 KV Pin insulators and 11 KV single / double break GOS, shall be procured by the agencies only from the BESCO approved vendors and other materials may be procured from authorized dealers of approved vendors to BESCO you have to utilize only polymer insulators as per corporate circular vide letter no BESCO/ BC-9/CGMCA/DCM(CA-3)/F-752/13-14/CYS 113. Dated 29.08.2013.

- 9) Guarantee shall be given by the developer for a period of one year for the materials used in the works as well as for the quality of work carried out, from the date of taking over of the distribution system and transformers by the BESCO.
- 10) Proof of having purchased the materials used for execution of works from the reputed firm will be verified wherever necessary.
- 11) You have to furnish the approval of Electrical Inspectorate for new HT / LT lines / DTCs etc., which ever applicable.
- 12) BESCO is not responsible in whatsoever manner regarding any of legal or local planning authority disputes that may arise at a later stage and deposits paid will be forfeited and power supply will be disconnected.
- 13) After payment of supervision charges and conditions to be fulfilled, the administrative approval will be issued from concerned Sub-division / Division / Circle office.
- 14) For all EHT and HT / LT lines passing through the layout safety clearance to be maintained (statutory) or shifting of existing lines to be done at your cost
- 15) You have to produce NOC from respective PGCIL/KPTCL in case if any EHV lines are passing in the layout before availing power supply to the layout.
- 16) You should clear the outstanding arrears if any of the installations inside the applicant premises.
- 17) You should abide by the conditions of supply of electricity of Distribution Licensees in State of Karnataka in force with subsequent amendments.
- 18) In future, the applicant has to pay any variation / difference of charges, if any, payable to BESCO.
- 19) The released materials, if any as per 7th schedule credit estimate shall be handed over to the concerned divisional stores.
- 20) After completion of work, joint inventory as prescribed vide chief Controller of Accounts, Circular No. AP/CYS-10/92-93/20-04-1992 (Page-246 of Compendium Vol-I) shall be taken and the assets shall be accounted in the books of company.
- 21) In case, if applicant fail to meet the above conditions to arrange power supply the Intimation letter is deemed to be cancelled.
Any delay in making the payment, not fulfilling the above payments within 90 days, the power sanction / application deemed to have been cancelled as per the conditions stipulated in the KEREC Amendment vide clause No. 4.03 (ii). The registration cum processing fee paid shall stand forfeited.
- 22) i. It is proposed to provide 1x250KVA DTC on 11Mtr spun pole.
ii. It is proposed to extend 3x95Sqmm XLPE HT UG Cable line about a distance of 100Mtrs as shown in the sketch.
- 23) iii. It is proposed to install LT Metering Cubicle.

Note: For any 765/400/220/66/11 KV lines passing adjacent/ nearby/ on the premises, mandatory clearance certificate should be obtained from the competent authority by the developer / concerned EE of BESCO before servicing of the installation. In case of any deviation in this regard concerned officers will be held responsible.

The above mentioned amounts should be paid within 90 days from the date of this letter at the Dabaspeta sub division failing which this intimation will be deemed to be cancelled. And payment certificate duly signed by the Assistant Executive Engineer, Dabaspeta Sub-Division to be sent to this office for communicating approval. Any delay beyond this would require renew of the feasibility which may please be noted.

Yours faithfully,


(Basavanna C)
Superintending Engineer (Ele),
BRC, BESCO, Bangalore

Copy to:

1. The Executive Engineer (Ele), C, O&M, Nelamangala BESCO for information.
2. The Assistant Executive Engineer (Ele), C, O&M, Dabaspeta Sub-division, BESCO for information.
3. MF/F-1(B).